

IMPLEMENTATION SEQUENCE:

1. CONSTRUCT NEW REUSE STORAGE BASIN
2. INSTALL AERATION AND DISINFECTION EQUIPMENT IN WEST LAGOON
3. INSTALL PIPING FROM WEST LAGOON TO NEW REUSE STORAGE LAGOON
4. DIRECT ALL WASTEWATER TO WEST LAGOON
5. REMOVE BIOSOLIDS AND WASTEWATER FROM EAST LAGOON
6. CLEAN AND LINE THE BOTTOM OF EAST LAGOON
7. INSTALL PIPING FROM WEST LAGOON TO EAST LAGOON TO USE EAST LAGOON AS FUTURE REUSE STORAGE
8. REMOVE BIOSOLIDS FROM WEST LAGOON WHILE IN OPERATION



XREFS: TB11X17, IMAGES: Lagoon Aerial.jpg

DATE: 3/9/09 TIME: 4:58:39 PM
 SERVER: SERVICE:
 PATH: \\CSB070002\SUPPLEMENTAL WASTEWATER PER\CAD\CIVL
 DRAWING NAME: WWO4.DWG
 PLOTTING VIEW:
 DESIGNER: MPT PROJ. MGR: WLK

NOLTE
 BEYOND ENGINEERING
 1976 RESEARCH PARKWAY, SUITE 105 COLORADO SPRINGS, CO. 80920
 719.299.8500 TEL. 719.299.8200 FAX WWW.NOLTE.COM

VILLAGE OF CIMARRON
 END RESULT OF WASTEWATER ALTERNATIVE 3
ONE TRAIN WEST LAGOON TREATMENT - EAST LAGOON/NEW BASIN STORAGE
 PREPARED FOR: VILLAGE OF CIMARRON DATE SUBMITTED: DEC. 2008

SHEET NUMBER
4
 OF 4 SHEETS
 JOB NUMBER
CSB070002